

OFFICE OF THE BOARD OF ADMINISTRATORS OF SANTIPUR MUNICIPALITY

(Estd. 1853)

P.O.- Santipur, Dist. - Nadia, Pin - 741404

Subrata Ghosh

Chairperson

Board of Administrators

Santipur Municipality



S.T.D. 03472

Phone : Office - 278029

Fax : 277170

Mobile : 9932916247 / 9153747647

OFFICE OF THE BOARD OF ADMINISTRATORS
OF SANTIPUR MUNICIPALITY

(Estd. 1853)

Santipur, Nadia, Pin - 741404

Ref. No. :

Date :

Ref.No : 12/5/22(03)

Date: 16.09.2021

Notice Inviting Quotation

Quotation on plain paper are invited from the reputed Companies/Firms/Contractors/agency for Single Brick Flat Soling work with PCC at Mahishkagitala, Ward no 12, Under Santipur Municipality under 14th FC. The quotation including of all tax and charges and have to submit within 25.09.2021 up-to 13.00 hours. Payment will paid from 14th FC fund after completion of the work.

SL. No.	Description of Item(s)	Quantity	Unit
1	Earth work in excavation of foundation trenches or drains, in all sorts of soil (including mixed soil but excluding laterite or sandstone) including removing, spreading or stacking the spoils within a lead of 75 m. as directed. The item includes necessary trimming the sides of trenches, levelling, dressing and ramming the bottom, bailing out water as required complete.(a) Depth of excavation not exceeding 1,500 mm.	18.980	Cum
2	Brick edging 75 mm wide with picked jhama bricks, laid true to line and level including cutting necessary trench in soil or in hard metalled surface, laying the bricks and repacking the trench (on both side of the edging) with spoils and ramming the same thoroughly complete as per direction.(b) Brick-on-end edging (250 mm) depth.	46.000	Meter
3	Single Brick Flat Soling of picked jhama bricks including ramming and dressing bed to proper level and filling joints with local sandSOR Vol-I:Building Works w.f.f 01/11/2017,	126.500	Sq.M.
4	Hire and labour charges for shuttering with centering and necessary staging upto 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof of ground floor)(f) 25 mm to 30 mm shuttering without staging in foundation	5.200	Sq.M.
5	Ordinary Cement concrete (mix 1:2:4) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement,if any, in ground floor as per relevant IS codes.a) Pakur Variety	7.610	Cum


Chairperson
Board of Administrators
Santipur Municipality
16/09/21

Ref.No : 12(5)/5/22(03)

Date: 16.09.2021

Copy forwarded for information and necessary action for wide publication in the notice board:-

1. The Post Master, Santipur Head Post Office, Santipur, Nadia.
2. The Station Master, Santipur Railway Station.
3. The Office Incharge, Santipur Police Station.
4. The Notice Board, Santipur Municipality.
5. The IT Cell for uploading the notice in the Santipur Municipality Web site.


Chairperson
Board of Administrators
Santipur Municipality
16/09/21