

# OF THE BOARD OF ADMINISTRATORS OF SANTIPUR MUNICIPALITY

(Estd. 1853)

P.O.- Santipur, Dist. - Nadia, Pin - 741404

**Subrata Ghosh**

Chairperson  
Board of Administrators  
**Santipur Municipality**



S.T.D. 03472

Phone : Office - 278029

Fax : 277170

Mobile : 9932916247 / 9153747647

OFFICE OF THE BOARD OF ADMINISTRATORS  
OF SANTIPUR MUNICIPALITY

(Estd. 1853)

Santipur, Nadia, Pin - 741404

Ref. No. : .....

Date : .....

Ref.No :14/05/22(DS)

Date: 27.08.2021

## **Notice Inviting Quotation**

Quotation on plain paper are invited from the reputed Companies/Firms/Contractors/agency for Water Bound Macadam Sub Base work in Agomeswari Street bye lane ,Ward no 4,Under Santipur Municipality under 14th FC. The quotation including of all tax and charges and have to submit within 07.09.2021 up-to 13.00 hours. Payment will paid from 14<sup>th</sup> FC fund after completion of the work.

SL. No.	Description of Item(s)	Quantity	Unit
1	Water Bound Macadam Sub Base by consolidating Jhama metal / Laterite chelly or stone metal/ shingles of specific size in hard crust to requisite thickness (measured after compaction) in layers including screening of metals etc. as necessary, hand packing, sweeping, watering and rolling in stages with power roller to proper line, grade and camber, lighting, guarding & barricading and making necessary earthen bundh of one metre width on each side where necessary to protect edges and preparing the bed by necessary cutting or filling and rolling all complete including the cost of all materials and hire and labour chargee fall men and machineries and compacting and to the required density, as per density, as per Clause 404 of Specifications for Road & Bridge Works of MoRT&H (5th Revision). [for construction of Sub base by consolidating Jhama metal (63 mm to 45 mm) with moorum screening	28.54	Cum
2	Cast in Situ Cement Concrete M20 Kerb. Construction of cement concrete kerb with top and bottom width 115 and 165 mm respectively, 250 mm high in M 20 grade PCC on M-10 grade foundation 150 mm thick, foundation having 50 mm projection beyond kerb stone, kerb stone laid with kerb laying machine, foundation concrete laid manually, all complete as per clause 409 of Specifications for Road & Bridge Works of MoRT&H (5th Revision). (The rate is inclusive of cost of all materials, labour, hire and usage charges of machinery and all incidental charges in this connection.) (A) Using Concrete Mixer	39.35	Meter



Chairperson

Santipur Municipality

Board of Administrators

Santipur Municipality

Date: 27.08.2021

Ref.No : 14/5/22(DS)/(5)

Copy forwarded for information and necessary action for wide publication in the notice board:-

1. The Post Master, Santipur Head Post Office, Santipur, Nadia.
2. The Station Master, Santipur Railway Station.
3. The Office Incharge, Santipur Police Station.
4. The Notice Board, Santipur Municipality.
5. The IT Cell for uploading the notice in the Santipur Municipality Web site.

Chairperson

Santipur Municipality

Board of Administrators

Santipur Municipality