

OFFICE OF BOARD OF COUNCILLORS OF SANTIPUR MUNICIPALITY

(Estd.-1853)

P.O.-Santipur, Dist-Nadia, Pin.-741404

S.T.D:03472

Phone:Office-278029

Santipur Municipality



e-mail:santipurmunicipality@gmail.com

Ref. No: 14/APAS

Date: 22.09.2025

QUOTATION NOTICE

Quotation No.- WBMAD/SM/APAS/02(1st Call)/2025-26

Reference No: SNT/PH-I/L-1/02081608/8557

The Executive Officer, on and for behalf of the Board of councillors of Santipur Municipality invites sealed offline quotation under APAS on Item Rate basis from reliable and resourceful Companies/Firms/Contractors having experience and acumen in Electrical work as noted below the eligibility as depicted hereunder for participating in the Bid.

Sl. No.	Event	:	Work details
1)	Name of the Work	:	Supply, Fitting and Fixing of 10 meter Mini Mast with 3 nos 120 W LED Light in Dhamodhar Mukharjee Street, Ward no 9 in Santipur Municipality under APAS, Booth no :121, Ward no:9 in Santipur Municipality under APAS.
2)	Location Details	:	Dhamodhar Mukharjee Street, Ward no 9 in Santipur Municipality
3)	Date & time of dropping of Quotation	:	14.10.2025 upto 1.00 PM
4)	Date & time of opening of Quotation	:	14.10.2025 upto 2.00 PM
5)	Place of issuance of Tender paper	:	Santipur Municipality
6)	Place of dropping and opening of Tender paper	:	Office of the Councillors, BOC, Santipur Municipality, Santipur, Dist:Nadia
7)	Contractors eligibility for participating in the Tender	:	Contractor Having experience for similar nature of work and technical acumen in Executing, same type of work in any Govt. Department /Board/Semi Govt./Corporation/Statutory Authority/Undertaking etc. Having annual turnover of at least Rs. 1 lakh or above in any one year of last Five Financial years. Having valid Trade License, Electrical License, P. Tax clearance Certificates, PAN Card, GST etc. Having Similar nature of works at least Rs. 40.00 thousand in a single work completed successfully within last Five years will be treated as credential.
8)	Tender of rate	:	Item Rate basis
9)	Time of completion	:	Work to be completed within 30 days

The intending bidders may see tender documents other relevant particulars during office hours on all working days at the Office of the Councillors, Santipur Municipality, Santipur, Nadia. Application should be submitted along with the proof of their current credential of satisfactory completion of similar nature of works at least Rs. 40,000.00 in a single work completed successfully within last Five years, valid PAN card, GST etc stated above. The tenderers shall have to produce original documents regarding proof of his credentials etc. During the quotation process L1 bidder has to submit 2% Earnest Money at the time of agreement in the form of the Bank Draft/or cash/pay order only from any nationalized bank and to be drawn in favour of the Executive Officer, Santipur Municipality otherwise the Quotation shall be rejected. bidder may remain present at the time of opening of tender.

The Executive Officer, Santipur Municipality, reserves the right to accept or reject any or all quotation without assigning any reason thereof.


Executive Officer
Santipur Municipality
Santipur Municipality

Dated: 22.09.2025

Memo no: 14(9)/APAS

Copy forwarded to :

1. The District Magistrate, Nadia.
2. The Additional District Magistrate(ZP), Nadia.
3. The District Nodal Officer, "Amader Para Amader Samadhan" Programme, Nadia.
4. The Sub-Divisional Officer, Ranaghat Sub-Division, Nadia.
5. The Executive Engineer, Nadia Division, ME Dte. 15 D.L. Roy Road, Krishanagar, Nadia.
6. The Executive Officer, Santipur Municipality.
7. The Finance Officer, Santipur Municipality.
8. The IT Coordinator for uploading the notice in the Santipur Municipality Web site.
9. Office Notice Board.




Executive Officer
Santipur Municipality
Executive Officer
Santipur Municipality

Details Specification of Supply, Fitting and Fixing of 10 meter Mini Mast with 3 nos 120 W LED Light in Dhamodhar Mukharjee Street, Ward no 9 in Santipur Municipality under APAS, Booth no :121, Ward no:9 in Santipur Municipality under APAS

Sl. No.	Item Description	Quantity	Units
1	Supply, Delivery at site of 10-meter G.I. octagonal pole is made from 3 mm thick galvanized steel, with a top across flats (A/F) of 70 mm and a bottom A/F of 175 mm. It is mounted on a 275 mm x 275 mm base plate with a 16 mm thickness, using 4-M24 bolts, each 750 mm in length, suitable for the pole's PCD. Make - Utkarsh/Calcutta Pole/ Bajaj	1	Each
2	Supply delivery at site single round arm bracket. Make - Utkarsh/Calcutta Pole/ Bajaj	1	Each
3	Supply delivery at site 120 watt LED flood light he luminaire operates at 140- 270 volt system wattages of 150W with an efficacy greater than 120 lm/W, providing a correlated color temperature of 5665K \pm 355K and a CRI above 70. It ensures 50,000 hours of lumen maintenance and operates within a temperature range of -10°C to 50°C, with a beam angle of 60° (\pm 10%). The unit is IP66- or above rated for dust and water protection, IK07-rated for impact resistance, with a power factor \geq 0.95, THD <10%, and surge protection of 4kV (built-in) and 10kV (external). Make- Bajaj/Philips/Havells/Crompton	3	Each
4	Errection of 1 no 10 meter long G.I. octagonal pole after preparation of RCC foundation of 400mm, 1500mm hight (1200 mm below the ground level and above 300 mm on ground) with required road, cement, chips, & sand etc at the ratio 1:1.5:3 with ground bolt.	1	Each
5	Hoisting fixing and commissioning of luminaries including making necessary connection and earthing attachment: HPMV/HPSV luminaries/LED fittings of any wattage.	3	Each
6	SUPPLYING OF FOLLOWING XLPE INSULATED ALUMINUM CONDUCTOR ARMORED CABLES OF 1.1KV GRADE AS PER IS 7098 (PART 1) 1988 WITH UP TO DATE AMENDMENTS. 2 core 6 sq mm cable	50	RM
7	Supplying and Drawing 1.1 KV single core stranded 'FR' PVC insulated & unsheathed single core stranded copper wire (Brand approved by EIC) of the following sizes in the prelaid polythene pipe and by the prelaid GI fish wire and making necy. connection as required 3 x 1.5 sq mm	40	RM
8	Laying only Cable upto 50 sqmm through existing RCC/Hume/ GI Pipe/open masonary trench for single, 2, 3, 3½ & 4 core.	30	RM
9	Laying of one No. cable upto 35 sqmm in underground trench 460 mm wide x 760 mm average depth, with brick protection on the top of the cable with 8 (eight) Nos. bricks per metre, including filling the space between the brick & cable and also the trench with shifted soil, leveling up and restoring surface duly rammed	20	RM
10	Earthing with 1588mm dia 1.8mtr long GI Earth Spike against each pole.	2	Each
11	Supplying and fixing compression type gland complete with brass gland, brass ring & rubber ring for dust & moisture-proof entry of XLPE/PVC armoured cables -For 2 core-upto 6 sqmm	2	Each
12	Finishing the end of following XLPE/PVC armoured cables by crimping method incl. supplying and fixing solderless socket (Dowels make), tapes, anticorrosive paste & jointing materials. 4 core 10 sqmm cable.	2	Each


Executive Officer
Santipur Municipality